



Shuklaphanta Municipality
Office of the Municipal Executive
Jhalari, Kanchanpur
Bill of Quantity

9
जुन १३/२०८२/२०८३
F/Y:-2082/2083

Name Of Project:- Krishi Bazar Gherbaar tatha Gate
Location :- shuklaphanta municipality ward 10

S.N	Description of Item	Unit	Quantity	Rate		Amount	Remark
				In Figure	In Words		
1	Clearing and grubbing land including uprooting rank vegetation, grass, bushes, shrubs, levelling surface & disposal of unserviceable materials as per instruction by site engineer.	sqm	84.47				
2	Excavation in soft clay and silty soil having lead upto 10m & lift upto 1.5m as per Drawing and Technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per instruction of the Engineer	cum	25.90				
3	Stone filling work in foundation trench & Levelling including 30 m lead/Used alternatively as soling as per instruction by site engineer.	cum	8.68				
4	Providing and Laying Plain Cement Concrete (P.C.C.) in 1:3:6 in foundation with cement, sand and aggregate including mixing, laying, finishing to approved level, line and dimensions and curing all complete as per specification and instruction by manual means	cum	11.60				
5	P.C.C. work 1:1.5:3 in Superstructure, Deck slab, Beam etc including 30 m lead using machine	cum	0.93				
6	Reinforcement bar cutting, Bending, Placing in position as per drawing, binding including lead upto 30m	kg	80.12				
7	Ms iron gate with ms angle and required iron sheet as per site inspection	kg	129.81				
8	Providing and laying 19 mm thick ply board including nail and other necessary material all complete for form works as per drawing including transportation up 30 m	sqm	99.61				
9	Supplying And Fixing zinc Coated Machine made square mesh of void size 75mmx75mm with 10swg mesh and 8swg border all complete As per instruction of site incharge.	sqm	274.86				
10	Providing and fixing MS Angel size - 50mm*50mm *6mm confirming to NS- IS code in as per detail drawings and specifications including straightening, ending, placing and binding with Gabion mat inproper directed by site incharge.	kg	546.19				
11	Providing and fixing MS Angel Patti size - 40mm *5mm confirming to NS- IS code in as per detail drawings and specifications and directed by site incharge	kg	163.30				
12	Providing and fixing nut bolt in proper directed by site incharge and including transportation of material upto 30m lead all complete works as per instruction by site engineer.	kg	8.92				
13	Providing and fixing barbed wire in 2 horizontal line in proper directed by site incharge and including transportation of material upto 30m lead all complete works as per site engineer.	kg	53.14				

Handwritten signature and text in the top right corner.

14	Supplying, Fitting and Installation of wiremesh, making and fitting of holdfast, accessibility of electricity and water, and other miscellaneous Works.	job	1.00			
		Sub-Total				
		Vat @ 13 %				
		Grand Total				

Name of Firm:

Address:

Signature:

Stamp: