


 प्रमुख प्रशासकीय अधिकृत
 आ.व: २०८२/०८३

योजनाको नाम : तटबन्ध र सडक स्तरे त्रिति
 योजना को स्थल : जयराज पैतोला को घर नजिक वडा नं ०५ र पोखरी टोल जाने सडक वडा नं ०३
 नगरपालिका : शुक्लाफाँटा नगरपालिका

SN	Description of Items	Quantity	Unit	Rate		Total Amount	Remarks
				Bidder's rate(In Digit)	Bidder's rate(In words)		
A Civil works							
1	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 30 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means , In area of light jungle (less than 15 number per 100 sqm) .	995.00	Sqm				
2	Earth work excavation in foundation, trenches in soft and medium soil including lift upto 1.5 m and disposal upto 10 m away from site as per need and specification all complete work.	10.80	Cum				
3	Supplying of Heavy Zinc Coating machine made gabion box of wire mesh Dia 3.00mm having 100mm*120mm double twist hexagonal mesh size selvedge wire Dia 3.9mm and Lacing Wire Dia 2.4mm (1.5*1*1/0)	15.00	Nos				
4	Supplying of Heavy Zinc Coating machine made gabion box of wire mesh Dia 3.00mm having 100mm*120mm double twist hexagonal mesh size selvedge wire Dia 3.9mm and Lacing Wire Dia 2.4mm.(3*1*1/2)	5.00	Nos				
5	Providing and filling stone/boulder in gabion boxes/mattress etc.. Including dressing, bedding, bonding all complete as per Drawing and Technical Specifications.	37.50	Cum				
6	Gravelling work for road width formation as per specified	46.61	Cum				
7	Providing and laying granular sub-base on prepared surface, mixing at omc, and compacting to achieve the desired density , complete as per Drawing and Technical specifications .	149.25	Cum				
Sub-total Amount							
Vat @ 13 %							
Contingency @ 2%							
Total Amount							

In words
 Name of Firm:
 Address of Firm:
 Authorized Signature and Date :
 Office Seal