



शुक्लाफाँटा नगर कार्यपालिकाको कार्यालय
भक्तारी, कञ्चनपुर
सुदूरपश्चिम प्रदेश, नेपाल
दररेट पेश गर्ने सम्बन्धि सूचना
सूचना प्रकाशित मिति : २०८३/०२/०८

१) शुक्लाफाँटा नगरपालिकाद्वारा विभिन्न निर्माण व्यावसायी सँग तपशिल बमोजिमको कार्य गर्नका लागि दररेट पेश गर्नका लागि यो सूचना प्रकाशित गरिएको छ ।

क्र.सं	विवरण	जम्मा रकम रु मु.अ.कर बाहेक	दररेट पेश गर्ने अन्तिम समय	कैफियत
१	वार्ड नं. ११ वडका विभिन्न सडक राम्रेल र तटबन्ध निर्माण कार्य	४३४०७९२२	२०८३/०२/१८ सायं ५:०० बजे सम्म	

२) दररेट पेश गर्ने निर्माण व्यावसायीले अनिवार्य रूपमा दररेट पेश गर्ने व्यहोरा सम्बन्धिको लिखित निवेदन सहित यस नगरपालिकाको आ.ब. २०८२/२०८३ मा सुचिकृत भएको प्रमाण, नविकरण भएको फर्म / कम्पनि दर्ता प्रमाणपत्रको प्रतिलिपि / नविकरण भएको व्यावसाय दर्ता प्रमाणपत्रको प्रतिलिपि / मु.अ.कर दर्ता प्रमाणपत्रको प्रतिलिपि र आ.ब. २०८१/२०८२ को करचुक्ता प्रमाणपत्रको प्रतिलिपि संलग्न गरि पेश गर्नुपर्ने छ ।

३) उक्त कार्यको लागि आवश्यक BOQ फाराम यस नगरपालिकाको वेबसाइट www.shuklaphantamun.gov.np बाट डाउनलोड गर्न सकिनेछ ।

४) BOQ मा आफुले कबोल गरेको रकम अंक र अक्षरमा स्पष्ट बुझिने गरि लेखेर पेश गर्नुपर्ने छ ।

५) पेश भइका प्रस्तावहरुको मुचुल्का २०८३/०२/१९ गते ११ बजे खोलिनेछ । फर्मको उपस्थिती नरहेमा कार्यालयले मुचुल्का प्रक्रिया अगाडी बढाउन कुनै बाधा पर्ने छैन ।

प्रमुख प्रशासकीय अधिकृत

Name Of Project:- Tek bahadur bohara najik sunbara najik uttar patti bato, tila sunarko ghar maji, garesh bahdur ayer ko ghar najik
Location :- ward no.11
Municipality :-Shuklaphanta Municipality

प्रमुख प्रशासकीय अधिकृत
शुक्लाफन्ता नगरपालिकाको कार्यालय

S.N	Description of Item	Unit	Quantity	Rate		Amount	Remark
				In Figure	In Words		
1	Earth work excavation in foundation, trenches in soft and medium soil including lift upto 1.5 m and disposal upto 10 m away from site as per need and specification all complete work as directed by site Engineer.	Cum	9.000				
2	Earth work filling in foundation, trenches in soft and medium soil including lift upto 1.5 m and disposal upto 10 m away from site as per need and specification all complete work as directed by site Engineer.	Cum	6.000				
3	Fabrication of Gabion Boxes Medium Zinc Coater GI Wire Hexagonal Mesh 100x120 Including rolling, cutting, weaving, assembling, placing in position stretching, packing with stone and binding all complete 1.5*1*1	Nos	15.000				
4	Fabrication of Gabion Boxes Medium Zinc Coater GI Wire Hexagonal Mesh 100x120 Including rolling, cutting, weaving, assembling, placing in position stretching, packing with stone and binding all complete 3*1*1	Nos	5.000				
5	Providing and filling stone/boulder in gabion boxes/mattress etc.. Including dressing, bedding, bonding all complete as per Drawing and Technical Specifications.	Cum	37.500				
6	Laying and fixing of Geo-Textile all complete as per specification. Providing and laying of a geotextile filter between pitching and embankment slopes as per Drawing and Technical Specifications.	Sqm	15.000				
7	Scarifying the existing road surface to a depth of 50 mm and disposal of scarified material with in all lifts and lead as per Drawing and Technical specifications & lead upto 30 m as per Technical Specification and directed by site Engineer.	Sqm	706.900				
8	Gravelling Work for road width formation with laying,spreading and compacting of each layer as per Technical Specification and directed by site Engineer.	Cum	208.200				
9	Providing and laying granular sub-base on prepared surface, mixing at omc, and compacting to achieve the desired density , complete as per Technical specifications and directed by site Engineer .	Cum	181.500				
			Sub-Total				
			Vat @ 13 %				
			Grand Total				

Name of Firm:

Address:

Signature: