Shuklaphata Municipality

Office of Municipal Executive

Jhalari, Kanchanpur

Sudurpachim Province, Nepal

प्रमुख प्रशासकीय अधिकृत

नगर कार्यपालिकाको कार्यालय
झलारी, कञ्चनपुर
सुदूरपश्चिम प्रदेश

BILL OF QUANTITY

Name Of Project:- वडा न. १० ईट्टा भट्टा पूर्व वडा न.९ जोड्ने बाटो,Nahar Paschim Padam Raj Paneruko Ghar Najik,Lalit Singh Thagunnako Ghar Jane Bato,Highway Dekhi Dakshin Nahar Keshab Kapadiko Gharbato

Location :- Shu.Na.Pa-Ward no.10

Municipality:- Shuklaphanta Municipality

F/Y:2082/83

SN	Description of Items	Quantity	Unit	Rate		Total Amount	Remarks
				Bidder's rate(In Digit)	Bidder's rate(In words)		
A	Civil works						
1	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 30 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means , In area of light jungle (less than 15 number per 100 sqm) .	970.50	Sqm				
2	Gravelling Work for road width formation with laying,spreading of each layer as per site engineer.	228.98	Cum				
					Sub-Total Amount		
					Vat @ 13 %		
					Total Amount		

In words:
Name of Firm:
Address of Firm:
Athorized Signature and Date :
Office Seal:

CamScanner