



प्रमुख प्रशासकीय अधिकृत

Shuklaphanta Municipality  
Office of Municipal Executive  
Jhalari, Kanchanpur  
Sudurpashchim Province, Nepal

Name Of Project - Mesh Wire Making And Warm Fertilizer Making Chamber Construction Work  
Location - Rasriya Ma Vi, Sitalpaha  
Municipality - Shuklaphanta Municipality Ward 04  
Contract No.

Bill of Quantity

FY/2080/091

	Description	Qty	Unit	Rate		Amount	Remarks
				In Figure	In words		
1	Excavation in soft clay and silty soil having lead upto 10m & lift upto 1.5m as per Drawing and Technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per instruction of the Engineer	24.43	Cum				
2	Stone filling work in foundation trench & Levelling including 30 m lead Used alternatively as soling as per instruction by site engineer	7.50	Cum				
3	Providing and Laying Plain Cement Concrete ( P.C.C ) in 1:3:6 in foundation with cement, sand and aggregate including mixing, laying, finishing to approved level, line and dimensions and curing all complete as per specification and instruction by manual means	7.05	Cum				
4	Brick Masonary Work in 1:4 c/s mortar	11.51	Cum				
5	Providing and laying 19 mm thick ply board including nail and other necessary material all complete for form works as per drawing including transportation up 30 m	35.60	Sqm				
6	Supplying And Fixing Zinc Coated Machine made square mesh(chain-link - fencing) of void size 75mmx75mm with 10swg mesh and border all complete As per instruction of site incharge	133.50	Sqm				
7	Providing and fixing MS Angel size - 50mm*50mm*6mm conforming to NS- IS code in as per detail drawings and specifications including straightening, ending, placing and binding with Gabion mat inproper directed by site incharge	321.90	Kg				
8	Providing and fixing MS Angel Patn size - 40mm*5mm conforming to NS- IS code in as per detail drawings and specifications and directed by site incharge	138.75	Kg				
9	Providing and fixing nut bolt in proper directed by site incharge and including transportation of material upto 30m lead all complete works	3.33	Kg				
10	Providing and fixing barbed wire in 2 horizontal line in proper directed by site incharge and including transportation of material upto 30m lead all complete works	72.98	Kg				
11	Supplying, Fitting and Installation of wiremesh, making and fitting of holdfast, accessibility of electricity and water, and other miscelleneous Works.	1.00	Job				
12	Mud Filling Work	133.33	Cum				
13	Plastering Work in 1:4 c/s Mortar	32.45	Sqm				
14	3 mm Thick Puning Work	32.45	Sqm				
	Total Estimate						
	VAT 13%						
	Grand Total Rs						

In words  
Name of Firm  
Address of Firm  
Athorized Signature and Date  
Office Seal: