


Name of project:- Construction of pashusewa kendra
 Location :- Ward No-01, Banashah
 Municipality :- Shukalaphanta Municipality 01.

Shukalaphanta Municipality
 OFFICE OF THE MUNICIPAL EXECUTIVE
 Kanchanpur
Quantity
 0832/2083
 १०८३२/२०८३
 १०८३२/२०८३
 १०८३२/२०८३

(Handwritten signature)
 १०८३२/२०८३

SN	Description of Item	Unit	Quantity	Rate		Amount	Remark
				In Figure	In Words		
1	Earth work excavation in foundation, trenches in soft and medium soil including lift upto 1.5 m and disposal upto 10 m away from site as per need and specification all complete work as directed by site incharge.	cum	5.569				
2	Earth work back filling in foundation, trenches (Earth transported from 10 m. surrounding) work in every 15-15 cm. layer with watering & proper manual compaction (except earth rate) as per the instruction of site engineer.	cum	12.554				
3	Stone/Boulder Soling work as per need and specification all complete work as per need and specification all complete work as directed by site incharge.	cum	6.077				
4	PCC work (1:3:6) as per need and specification all complete work as directed by site incharge.	cum	5.684				
5	Providing and laying Brick masonry work in 1:4 cement sand mortar with first class local chimney bricks as per need and specification all complete work as directed by site incharge.	cum	4.244				
6	Fixing of porcelain glazed tile in 1:4 cement mortar for floor as per need and specification all complete work as directed by site incharge	Sqm	33.996				
7	Plastering work with 1:4 CM as per need and specification all complete work as per need and specification all complete work as directed by site incharge.	Sqm	8.588				
8	Supplying and applying of two Plastic emulsion paint (Internal) over one coat primer on inner plaster surface including cleaning and scaffolding all complete as per specification and instruction.	sqm	229.231				
9	Electrification work as per need and specification as per specification and instruction.						
	48" ceiling fan	nos.	4.000				
	dimmer	nos.	4.000				
	PAC bulb 9 watt	nos.	6.000				
10	Supplying and fixing of MS grill works with primer coating and painting as per need and specification all complete work as directed by site incharge.	Sqm	14.336				
11	Making and fixing of Well seasoned Sal wood work for Door pannelled with all complete works as per instruction by site incharge.	Sqm	4.200				
12	Making and fixing 4 mm thick White glazed shutter (1.829m x 1.22m) for window using sal wood frame of the size : 38 mm x 75 mm as per need and specification all complete work as directed by site incharge	Sqm	14.336				
13	38mm thick (1:2:4) P.C.C.(DPC) for flooring with punning, rubbing in hard surface curing as per need and specification all complete work as directed by site incharge.	Sqm	29.045				

14	Making and fixing of Readymade modern teak wood work for Door pannelled with all complete works as per instruction by site incharge.	5,670		
15	Making and Fixing of tubular truss with primer and painting works at all complete work as per instruction of site engineer	73,175		
16	Making and fitting of 26 gauge colourfull CGI roofing sheet with need and specification all complete works as per instruction by site engineer.			
Sub-Total				
Vat @ 12%				
Grand Total				



Handwritten signature or initials

वडा कार्यालय

Name of Firm:

Address:

Signature:

Stamp: