

Suklaphanta Municipality  
Office of Municipal Executive  
Jhapa, Kanchanpur  
Sudurpashchim Province, Nepal

BILL OF QUANTITY

*[Signature]*  
Date: 2082/83

Name of Project : Shiv Mandir Nirman And gabion Work  
Location : su na pa 09  
Municipality : Suklaphanta Municipality

SN	Description of Items	Quantity	Unit	Rate		Total Amount	Remarks
				Bidder's rate(In Digit)	Bidder's rate(In words)		
A Civil works							
1	Excavation in soft clay and silty soil having lead upto 10m & lift upto 1.5m as per Drawing and Technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instrution of the Engineer	18.00	Cum				
2	R.C.C. 1:1.5:3 work as per need and specification all complete work as directed by site incharge.	8.20	Cum				
3	Form work as per need and specification all complete work as directed by site incharge.	76.54	Cum				
4	Reinforcement Work as per need and specification all complete work as directed by site incharge.	451.49	Cum				
5	Providing and laying Brick masonry work in 1:6 cement sand mortar with first class local chimney bricks as per need and specification all complete work as directed by site incharge.	2.11	Kg				
6	Supplying of Heavy Zinc Coating machine made gabion box of wire mesh Dia 3.00mm having 100mm*120mm double twist hexagonal mesh size selvedge wire Dia 3.9mm and Lacing Wire Dia 2.4mm. (3X1X0.5/2)	40.00	Sqm				
7	Providing and filling stone/boulder in gabion boxes/mattress etc.. Including dressing, bedding, bonding all complete as per Drawing and Technical Specifications.	72.00	Cum				
	Laying and fixing of Geo-Textile all complete as per specification	24.00	sqm				
<b>Sub-total Amount</b>							
<b>Vat @ 13 % Exculding ps</b>							
<b>Contingency @ 2%</b>							
<b>Total Amount</b>							

In words:  
Name of Firm:  
Address of Firm:  
Athorized Signature and Date :  
Office Seal: